

Hubbell SnapConnect™ Receptacle Terminals

Instructions for Checking Correct Wiring

Supplementary Instruction Sheet for Reference by Technical Services Department. Provided Upon Request.

GENERAL INFORMATION

CAUTION: RISK OF ELECTRIC SHOCK.

- The following test procedure is conducted when the circuit is energized.

NOTICE: To be conducted by a qualified person in accordance with national and local electrical codes.

WIRING INFORMATION

- The correct wiring of an installed terminal can be verified with a common voltmeter using the test method below. The test can be performed without removing the protective polybag by inserting the tester probes through the opening in the bag.
- Lightly insert voltage meter probes into appropriate holes on face of terminal connector to just touch the contacts.
- Observe the voltage readings as shown below. **DO NOT** force probe into the contacts or the contacts may be damaged.

